


AUTOMATION SYSTEM FOR CONCRETE PREFAB MANUFACTURING



1. Production Process

Concrete Prefab Automation

Production process machinery and automation systems for manufacturing concrete prefab components
 Computer-controlled operations provide flexibility to accommodate various shapes and sizes of products.
 Process continuity is achieved through automated control technology that reflects actual field conditions.



Mold Assembling System
 Mold transfer and placement automation technology using the gripper

Concrete Distributor
 Automatic concrete pouring technology for placed molds

Surface Finishing Machine
 Automatic finishing technology to ensure consistent top surface quality after concrete pouring


Tunnel-type Curing Chamber
 Curing management technology through individual temperature and humidity control in curing chambers

Mold Assembling System
 Loading and assembly of molds

Distributor
 Concrete pouring

Curing Chamber
 Curing of Materials

Finishing machine
 Material surface finishing



2. Technical Background

Existing System




Development System

Integration with a quality management system

Development of automated production equipment and control systems
Variable-setting automation for mold placement, finishing, and production processes

Data-based development of drive and control interface technology

Shape-variable smart mold technology



3. Features of Technology

Productivity

Total productivity increased by more than 30%

30% ↑

Production Time

Before system application
3 hours

After system application
2 hours

Manpower

Before system application
6 persons

After system application
3 persons

Improved Safety

Improved safety with a 50% reduction in accident rates

50% ↓

Before system application



After system application



Customized Production

Flexible production of various shapes and sizes through CAD/CAM integration

Quality Consistency

Ensured quality consistency through the reduction of human error

Production Cycle

Optimized production cycles through data-driven production management

Eco-friendly

Optimized concrete usage reduces material waste and improves energy efficiency



ING

Global Market Development



4. Production Process

Step 1
PLC equipment control



Step 4
Mold positioning and setting



Step 2
Mold loading (using RFID)



Step 5
Flying bucket concrete pouring



Step 3
Move mold to gripper



Step 6
Concrete distributor installation



4. Production Process

Step 7
Vibrator compaction



Step 8
Screed surface finishing



Step 9
Rotary surface finishing



Step 10
Transfer cart movement



Step 11
Tunnel-type curing chamber operation




Step 12
Demolding and product transfer




Layout

Top View



Side View




5. Equipment Introduction

Control System

Drive Control Solution

In response to variations in product shape, users can easily optimize available mold arrangements on the PC screen. A PLC-linked control program is automatically generated, eliminating the need for on-site pre-setting of equipment operation parameters.



Mold Assembling System

Side Mold

The side mold is the outermost structure designed to withstand the lateral load of concrete filled inside the prefab mold. High-strength permanent magnets are applied to secure the mold against heavy concrete pressure.



- Function**
- Structure capable of withstanding lateral concrete loads
 - Permanent magnet descends to secure the mold
 - Magnet is released by lifting via top-mounted adjustment nut

- System Components**
- 2,000 kg permanent magnets (2 EA)
 - Magnet lowering and lifting nuts
 - Hydraulic cylinder press

5. Equipment Introduction

Gripper


- Position the mold precisely in the placement coordinates and press the magnetic pin to secure the mold
- Automatically recognize the mold transferred to the roller and load it into the load box and remember its location



Function

- Automatic mold positioning using PC-transmitted coordinates
- Grip range : 54-294 mm
- Maximum transport weight : 300 kg

1. Move to pick up location
2. Pick up mold
3. Move to placement coordinates
4. Place mold
5. Press magnet pin
6. Return to standby position




Concrete Distributor

Concrete is transported and poured according to received discharge coordinates. The discharge system consists of six independently controlled motors, enabling precise control of concrete discharge volume. The interior of the distributor body is automatically cleaned after operation.



Function

- Maximum storage capacity : 2,100 L
- Maximum discharge rate : 760 L/min (assuming a 30% material loss rate)
- Six independent discharge outlets



1. Servo motor
2. Outlet
3. Inside the body
4. Screw
5. Outlet (closed)
6. Outlet (open)
7. Concrete pouring
8. Washing and drainage

5. Equipment Introduction

Surface Finisher

After concrete pouring, a vibrating finishing blade descends to level the surface. The blade then moves in contact with the concrete to complete surface finishing.



Components

- Finishing blade
- Z-axis rack and pinion
- Z-axis AC drive motor
- Finishing blade vibration motor

Motor

- Excitation force: * 120 kgf
- Frequency : 60 Hz
- Output : 100 W

* Excitation force refers to the fundamental force that induces vibration.



Screed Finisher



Rotary Finisher

Tunnel-type Curing Chamber

The curing chamber is a device that performs wet curing of prefab products. After sealing the chamber, the boiler operates and steam is injected to maintain a temperature of 60 °C under controlled humidity conditions.



Function

Steam injection with air curtain to maintain stable temperature and humidity

Process

1. Mold base is transported to the limit sensor inside the curing chamber
2. Curing chamber door is closed (each chamber operates independently)
3. Boiler starts operation and steam is injected through wall-mounted nozzles
4. Temperature is gradually increased and maintained at 60 °C
5. PLC automatically controls optimized curing conditions




5. Equipment Introduction

Central Control System


- Overall control and monitoring of the entire production line
 - PLC control system
 - PC control system with user graphic interface

System Configuration Diagram



Utilities


- Main power supply : AC 400 V / 60 Hz / 3-phase
- Control power : AC 220 V / DC 24 V
- Compressed air : minimum 8 kgf/cm², approx. 40 Nm³/h, maximum moisture 60%



6. Technical Applications

Bridge

Bridge floor slabs




Tunnel

Tunnel duct slabs




Tunnel segments



Retaining Wall

Precast retaining walls



* Applicable to the production of precast concrete components in various construction fields



NDT ENGINEERING & AEROSPACE CO., LTD.

NDT Engineering & Aerospace Co., Ltd.

Automation System for Concrete Prefab Manufacturing

11, Jayumuyeok 4-gil, Masanhoewon-gu, Changwon-si, Gyeongnam, 51343, Korea

www.ndteng.co.kr

Printed in Korea
December 2025